

### Acknowledgment of Country

We begin our commitment to reconciliation by acknowledging the Traditional Owners of the land on which we meet today.

We pay respect to Elders past and present.





### Agenda


Acknowledgment of CountryIntroductionsProject overviewHumeLink EISPublic exhibitionQuestions/discussionNext steps and close





## HumeLink project overview: what is HumeLink?


- HumeLink is a new 500kV transmission line • which will connect Wagga Wagga, Bannaby and Maragle
- It is one of the state's largest energy • infrastructure projects, with about 360 km of proposed new transmission lines, and new or upgraded substation infrastructure at four locations.



### Concept design: transmission lines and structures


The project includes the construction of 500 kV transmission line sections between:

- Wagga 330 kV substation and the proposed Gugaa 500 kV substation
- Proposed Gugaa 500 kV substation and Wondalga
- Wondalga and the future Maragle 500 kV substation
- Wondalga and Bannaby 500 kV substation.



<sup>500</sup> kV double circuit steel tower







### Concept design: substations

- Wagga Wagga 330 kV substation
- Bannaby 500 kV substation
- Proposed Gugaa 500 kV substation.

Future Maragle 500 kV substation\*







### HumeLink project overview: key dates











### **Environmental Impact Statement**



### HumeLink EIS – Planning approval pathway





HumeLink receives Ministers' Conditions of Approval which Construction Environmental submitted to DPE for approval before construction



### What is an Environmental Impact Statement?

HumeLink is a Critical State Significant Infrastructure (CSSI) project and an Environmental Impact Statement (EIS) has been prepared for approval by the NSW and Commonwealth Governments.

The EIS outlines:

- potential economic, environmental and social impacts of the project •
- environmental mitigation measures to address identified impacts •

The EIS was lodged with the NSW Department of Planning and Environment (DPE) on Friday 25 August 2023

The EIS was placed on public exhibition by DPE from Wednesday 30 August 2023 and can be accessed via the NSW Major **Projects Planning portal** 

During the public exhibition period, the community has an opportunity to have their say on the project via a formal submission to the DPE.





### What have we assessed?










Electric and magnetic fields





### EIS Overview – Landscape Character and Visual Amenity

#### **Assessment outcomes**

Impacts	Mitigation measu
<ul> <li>180 dwellings are either located within the project footprint or within 500m of it, of which: <ul> <li>17 dwellings would have high visual impact</li> <li>27 dwellings would have a high-moderate visual impact</li> <li>36 dwellings would have a moderate visual impact</li> </ul> </li> <li>Moderate visual impacts from Snowy Mountains Highway, Gocup Road and Brungle Road.</li> </ul>	<ul> <li>Opportunities for retention and prot vegetation will be identified during of Near Neighbours – engagement wit adjacent landowners who might be visual amenity perspective</li> <li>Consultation with landowners idention moderate to high visual impact to en- specific mitigation measures.</li> </ul>

#### ures

otection of existing g detailed design

with e impacted from a

ntified to have a evaluate property-



## EIS Overview – Landscape and visual – public viewpoints



View south from Snowy Mountains Highway

View south-east from Brungle Road



## EIS Overview – Landscape and visual – public viewpoints



View west from Bannaby Road

View south from Cooks Hills Road



## EIS Overview – Land Use and Property

#### Impacts

- Changes in land tenure from property acquisition and establishment of easements (including loss of agricultural land)
- Minor temporary impacts on property access during construction
- Fragmentation of land parcels during construction and operation
- Potential removal or adjustment of structures
- Restrictions within the transmission line easement for some agricultural, forestry and other activities
- Potential biosecurity impacts
- Temporary restrictions to livestock and vehicle movements during construction
- Potential disruptions to on-ground, aerial and irrigation operations
- Potential radio communication and global positioning system (GPS) interference.

### **Mitigation measures**

- for directly impacted landowners to manage construction impacts
  - 0 tracks
  - Property access requirements 0
  - Management of livestock movements Ο
  - Property operational requirements Ο
  - **Biosecurity controls** Ο

#### PMPs to be developed in consultation with landowners.

- Disturbed areas would be stabilised and appropriately rehabilitated following the completion of construction at each location.

Development and implementation of property management plans (PMPs) Establishment and use of temporary and permanent access

Any requirements related to the ongoing operation and maintenance of the easement would be agreed in consultation with affected landowners and will follow Transgrid's standard operating procedures and protocols.



### EIS Overview – Bushfire Risk

### **Potential impacts**

#### **During construction:**

- Construction activities involving hot works
- Construction equipment such as bulldozers and excavators
- Motor vehicle exhaust systems especially diesel-powered trucks and light vehicles
- Electrical faults in equipment
- Inappropriate storage and handling of dangerous materials.

#### **During operation:**

- As above
- Substation and transmission line operation if mechanical failure or direct or indirect contact (if within safety clearance space) with vegetation occurs
- Accidental ignitions caused by plant, equipment, motor vehicles or hot works during maintenance activities.

- Control for risks through engineering design in line with construction • requirements
- Control for risks through land management, with reference to Asset include:
  - 0 worker accommodation facilities
  - 0 in accordance with

#### **Mitigations**

Protection Zone (APZ) and in consideration of land features such as slope, vegetation and climate, and transmission line clearances. These

Outlining the APZ around substations, construction compounds and

Managing vegetation within the proposed transmission line easement

Transgrid's existing vegetation management plans.

Emergency preparedness and response procedures,

including a project specific Bushfire Emergency

Management and Evacuation Plan (BFEMEP).



### EIS overview – Biodiversity

#### Assessment outcomes

Assessment carried out adopts a precautionary (i.e., conservative) approach, especially where there are unknowns. May lead to scale of impacts looking worse. There are opportunities for impact reduction during design refinement.

Impacts	Impacts Mitigation measures
Loss of vegetation from clearing Loss of habitat for threatened ecological communities or fauna species Disturbance to wildlife from construction activities Spread of weeds, pests and pathogens Sedimentation impacts on water quality affecting aquatic species Habitat fragmentation from the creation of an easement Potential fauna collisions or electrocution due to the transmission lines.	<ul> <li>Design – refinement of the disturbance footprint during detailed design and construction</li> <li>Construction – a Biodiversity Management Plan will be developed as part of the CEMP. Will be supplemented b         <ul> <li>Construction – a Biodiversity Management Plan will be developed as part of the CEMP. Will be supplemented b             <ul> <li>Construction – a Biodiversity Management Plan will be developed as part of the CEMP. Will be supplemented b                <ul> <li>Connectivity Strategy</li> <li>Hollow and Nest Strategy</li> <li>Other measures in the CEMP to address erosion and sedimentation, air quality, noise, and traffic impacts.</li> <li>Operations – Transgrid guidelines and procedures for maintenance including vegetation management</li> <li>Residual biodiversity impacts will be offset in accordance</li> <li>Residual biodiversity impacts will be offset in accordance</li></ul></li></ul></li></ul></li></ul>



Example of Alpine wetland/ fen habitat



/ a:

### EIS Overview – Traffic and Transport

#### Assessment outcomes

	Impacts
Construction	<ul> <li>Temporary increase in traffic movements on roads connecting work sites for the duration of construction activities – variable activity due to multiple work fronts         <ul> <li>Transport of construction materials and equipment, waste and spoil</li> <li>Transport of construction materials and equipment from multiple</li> </ul> </li> </ul>
	locations using national, state and local road networks, as well as access tracks (including light and heavy vehicles, and in some instances over-size and over-mass vehicles)
	<ul> <li>Construction work to occur in a progressive manner along the project footprint</li> <li>Road network performance</li> </ul>
	<ul> <li>Assessment done based on level of service</li> </ul>
	<ul> <li>Study area is expected to maintain the same level of performance</li> </ul>
	<ul> <li>Temporary land and road crossing during transmission line stringing.</li> </ul>
Operation	<ul> <li>Infrequent movements across the project footprint and the surrounding transport network – for maintenance, easement inspection.</li> </ul>

#### **Mitigation measures**

- Regular communication on construction traffic with the relevant road and rail authorities, community and motorists, landowners and project stakeholders
- Development of a Traffic and Transport Management Plan (TTMP) (part of the CEMP)
- Dilapidation surveys prior to construction work to evaluate current condition of the road surface (on local roads only)
- Subsequent road condition assessment at the completion of project construction and rectification of any damage caused by the project.



## EIS overview – Aboriginal heritage

#### Assessment outcomes

Impacts	Mitigation measures
<ul> <li>Precautionary approach adopted</li> <li>Summary of ACHAR findings for the project footprint:         <ul> <li>90 Aboriginal heritage sites (incl. 79 stone artefact sites)</li> <li>Eight potential archaeological deposits</li> <li>Three modified trees</li> <li>Does not impact known Aboriginal reserves or early historical properties where documented significant historical interactions with Aboriginal people occurred</li> <li>One significant Women's site identified at Derringullen Creek will be avoided.</li> </ul> </li> </ul>	<ul> <li>Impacts would be reduced through implementation of the avoid, minimise and mitigate principles.</li> <li>Heritage Management Plan will be developed with RAPs and implemented as part of the CEMP:         <ul> <li>Where impacts cannot be avoided, surface artefacts and subsurface deposits may be salvaged, in consultation with RAPs, as a measure to mitigate harm</li> <li>Unexpected finds procedure</li> <li>Heritage monitoring.</li> </ul> </li> </ul>



Example of a scarred tree



### EIS overview – Noise and vibration

#### Assessment outcomes

		Impacts	
Со	onstruction	<ul> <li>Noise from site establishment work including vegetation clearing, civil works for new access tracks or compounds, and laydown areas</li> <li>Noise arising from:         <ul> <li>construction of transmission lines – use of plant and equipment, concrete batching, erection of steel components</li> <li>construction of new substation and modification of existing substations – civil works, erection of new buildings and steel structures</li> </ul> </li> <li>Vibration impacts from construction equipment</li> <li>Construction traffic noise.</li> </ul>	<ul> <li>Construction the source and vibration</li> <li>Equipmention</li> <li>We on Noise and</li> </ul>
Op	peration	<ul> <li>Audible noise from the operation of high voltage transmission lines (corona noise) - noticeable under certain weather conditions</li> <li>Noise arising from the operation of the new substation (from transformers or shunt reactors)</li> <li>Trigger levels (determined in accordance with NPfI definitions)         <ul> <li>'Intrusive' noise impacts</li> <li>Land use amenity.</li> </ul> </li> </ul>	<ul> <li>Operational be manage including s</li> <li>Operational noise impara design and the transm</li> </ul>

### Mitigation measures

tion noise to be managed at the to reduce the potential noise ation impacts from the project. Int selection Vork hours Noise screens d Vibration Management Plan (NVMP).

hal substation noise to ged by incorporating design measures selection and positioning of equipment. hal transmission line bacts to be considered during detailed hd confirmed with noise monitoring once mission lines are operational.



## EIS overview – Air quality

#### Assessment outcomes

Impacts	Mitigation measures	- 485
<ul> <li>Earthwork and vegetation removal</li> <li>Establishment and use of construction compounds and worker accommodation facilities</li> </ul>	<ul> <li>Water spraying for dust suppression</li> <li>Locating dust generating activities away from receivers</li> <li>Protection and strategic location of</li> </ul>	
<ul> <li>Construction and use of access tracks</li> <li>Movement of vehicles to and from construction areas including exhaust fumes</li> <li>Main construction work for project</li> </ul>	<ul> <li>stockpiled materials</li> <li>Covering loads when transporting dust</li> </ul>	
infrastructure.	<ul> <li>disturbance and stabilising disturbed areas as soon as practicable</li> <li>Planning and scheduling vegetation clearance.</li> </ul>	A wa





vater cart used to control dust on construction sites



### EIS overview – Social

#### Assessment outcomes

	Impacts		Mit
Construction	<ul> <li>Reduced availability of accommodation from increased demand from construction workers</li> <li>Temporary construction impacts including traffic and amenity (from dust, noise, vibration)</li> <li>Localised and temporary visual amenity impacts from construction activities</li> <li>Temporary increase in the demand for goods and services</li> <li>Positive benefits from employment and upskilling opportunities.</li> </ul>	•	Investigation of add facilities Consultation with lo Ongoing engageme landowners, the cor Individual Property
Operation	<ul> <li>Opportunities for investment through Transgrid's support initiatives</li> <li>Potential visual amenity impacts from permanent infrastructure</li> <li>Potential impacts to farming operations and businesses from acquisitions, easements and temporary leasing arrangements.</li> </ul>	•	Opportunities for re- existing vegetation Tailored plans to ma achieve a positive le

### itigation measures

#### ditional temporary worker accommodation

- ocal service providers
- nent with affected
- ommunity, and interested organisations
- Management Plans (PMPs).

etention and protection of will be identified during detailed design nanage impacts, promote opportunities and legacy.



### EIS overview – Economic

#### Assessment outcomes

	Impacts	Mitig
Construction	<ul> <li>Employment opportunities during construction</li> <li>Increase in expenditure for local businesses and retailers</li> <li>Investment return through increased demand for temporary accommodation</li> <li>Tourism (local expenditure and availability)</li> <li>Housing availability</li> <li>Temporary impacts on agricultural productivity including impacts on forestry land.</li> </ul>	<ul> <li>Temporary worker short-term rental a</li> <li>Tailored manager economic impacts Accommodation S</li> </ul>
Operation	<ul> <li>Contribution to net market benefits</li> <li>Increased competition in wholesale energy</li> <li>Help lower and stabilise electricity prices, reduce volatility in the longer term</li> <li>Impacts on land productivity.</li> </ul>	<ul> <li>Economic impacts of productive land through easement</li> </ul>



### gation measures

er accommodation to ease demand on accommodation ement plans to manage and reduce ts (including a Worker Strategy).

s associated with direct loss d would be minimised it compensation.



### EIS overview – Soil and Contamination

#### **Assessment outcomes**

	Impacts	Mitigati
Construction	<ul> <li>Soil erosion and sediment transport from excavation, vegetation removal and vehicle movements</li> <li>Salinity impacts from exposure of saline soils during earthwork</li> <li>Mobilisation of asbestos fibres (potentially impacting human health).</li> </ul>	<ul> <li>Mitigation measures Environmental Man Soil and Water Man</li> <li>Risk of unexpected unexpected contar</li> </ul>
Operation	<ul> <li>Little risk of soil erosion and transport of sediment due to minimal exposed topsoil</li> <li>Long-term minor salinity impact due to changes to soil profile</li> <li>Localised contamination from vehicle accidents, leaks and spills.</li> </ul>	<ul> <li>Transgrid's existing framework.</li> </ul>



#### tion measures

es in the Construction nagement Plan and associated anagement Plan d contamination managed via mination finds protocol.

g environmental policies and



### EIS overview – Waste

#### **Assessment outcomes**

	Impacts	Mitigati
Construction	<ul> <li>Waste generated from clearing/removing vegetation, earthwork activities, workers, and excess construction material</li> <li>Types, quantities and classifications of waste generated would vary and be confirmed during construction.</li> </ul>	<ul> <li>Management of conspecified in the Was prepared as part of</li> </ul>
Operation	<ul> <li>Minimal waste expected during operation including electrical components from maintenance, oil and green waste from vegetation maintenance, and wastewater from substation operation.</li> </ul>	<ul> <li>Minimal waste to be Transgrid's existing System and process</li> <li>All waste for offsite by an authorised co appropriately licens</li> </ul>



### ion measures

onstruction waste would be aste Management Plan of the CEMP.

be managed in accordance with g Environmental Management esses

e disposal would be collected contractor and taken to an

sed waste facility.



## EIS overview – Surface Water and Groundwater

#### **Assessment outcomes**

	Construction Impacts	Operational Impacts
Water supply and management	<ul> <li>Non-potable water for dust suppression</li> <li>Potable water for worker accommodation</li> <li>Wastewater generated to be collected and disposed at local wastewater treatment plants.</li> </ul>	<ul> <li>Non-potable water required for maintenance activities and substation operation.</li> </ul>
Water quality, erosion and sedimentation	<ul> <li>Surface water (impacts from vegetation clearing, excavation and earthworks, stockpiling of soil and construction materials).</li> </ul>	<ul> <li>Impacts would vary depending on the location and proximity to sensitive receiving environments.</li> </ul>
Geomorphology	<ul> <li>Short-term and limited impacts from dirt and runoff next to and into waterways</li> <li>Installation of waterway crossings.</li> </ul>	<ul> <li>Impacts limited to the Bannaby 500 kV substation and permanent waterway crossings.</li> </ul>



#### **Mitigation measures**

- rosion and Sediment Control Plan (ESCP) uring construction
- cour (washout) protection in the design of frastructure sitting within waterways
- later quality monitoring during construction
- Vater supply and management agreements etween delivery partners and water sers/suppliers
- Construction methodology focused on ninimising impacts.



## EIS overview – Electric and Magnetic Fields

#### What does this study assess?

The assessment included modelling of different sections of the transmission lines as well as where the transmission lines would intersect or parallel other existing transmission lines. A separate assessment of EMF at the substations was also completed.

	Assessment outcomes		
Transmission lines	<ul> <li>The contribution of the proposed 500 kV lines to the magnetic field environment is expected to be well below the International Commission on Non-Ionizing Radiation Protection (ICNIRP) Guideline Reference Level</li> <li>The electric fields directly below the transmission lines would comply with the Basic Restrictions under the ICNIRP guidelines</li> </ul>	Fridge 2–5 mG VID Kettle 2–10 mG	Stove 2–30 mG Under a distribution line 2–20 mG
Substations	<ul> <li>Gugaa 500 kV substation designed to ensure that the EMF complies with the relevant ICNIRP guidelines         <ul> <li>Enclosed by a security fence and access to the substation would be controlled to authorised persons only</li> </ul> </li> <li>Modifications to the existing Wagga 330 kV and Bannaby 500 kV substations would be designed to ensure EMF levels are also below the adopted criteria</li> </ul>	• •	<b>fence</b> 1-8 mG

27



Toaster 2–10 mG

Laptop

2-20 mG

Hairdryer

10-70 mG

-



**Electric blanket** 5-30 mG



**Directly under** high voltage transmission line 10-200 mG


#### Management Measures

- Reduce intensity of EMF • by locating lines away from residences to minimise ongoing public exposure
- Studies have found no • detectable effect from **EMF** emissions from transmission lines on crops, farm animals or natural ecosystems




magnetic fields measured iances and powerlines

## Cumulative impacts



### Environmental management approach




COMMUNITY AND STAKEHOLDER ENGAGEMENT MANAGEMENT PLAN ENGAGEMENT IN ACCORDANCE WITH TRANSGRID

OPERATIONAL PROCEDURES AND GUIDELINES





### **Public exhibition**



### EIS Public exhibition – Information available on HumeLink EIS

Level and complexity of information presented

#### Community Resources

Information including webinars, FAQs, fact sheets, juidelines, videos, presentations, briefings and newsletters.

Available on the HumeLink website.

#### HumeLink EIS Summary

A Summary Report providing a high-level introduction to the project and the EIS assessment outcomes.

Available on the NSW Major Projects Planning Portal.

#### **Digital EIS**

A user-friendly and interactive digital platform to present key EIS findings. Includes interactive mapping, multi-media and links to the full EIS on the NSW Planning Portal.

Available on the HumeLink website.

#### **EIS Chapters and Appendices**

The main volume of the report that meets the requirements of the Planning Secretary's Environmental Assessment Requirements (SEARs) and Supplementary SEARs. The chapters present a summary of the assessment outcomes from the various technical studies. Refer to Chapters 1-28 and Appendices A-E of the EIS.

Available on the NSW Major Projects Planning Portal and at selected council libraries.

#### **EIS Technical Reports**

A detailed assessment of EIS topics as required by the SEARs and Supplementary SEARs.


These reports outline the potential significance of project related impacts and the proposed mitigation measures to avoid, manage or minimise them. Refer to Technical Reports 1-18 of the EIS.

Available on the NSW Major Projects Planning Portal.





### Community information sessions



### EIS Public exhibition – How to make a submission



How to make a submission to the NSW Department of Planning and Environment (DPE)

#### Online

- **1** Visit the NSW DPE Major Projects Planning Portal: www.planningportal.nsw.gov.au/major-projects
- 2 Create a Major Projects account by clicking the 'Sign in' button
- **3** Search for the HumeLink project
- 4 Click the 'Make a submission' button

#### Post

Post your hard-copy with both the mailing envelope and submission addressed to:

Director – Energy Assessments Planning and Assessment Department of Planning and Environment Application number: SSI-36656827 Locked Bag 5022 Parramatta NSW 2124

The EIS public exhibition process for the HumeLink project is run by the NSW Department of Planning and Environment (DPE). All submissions must be addressed to the Department and must be made within the public exhibition period.





### EIS Public exhibition – How to make a submission

#### Writing tips



A submission can be written in bullet points or full sentences



A submission can be written in plain-English and does not require technical expertise

#### Submission criteria



A submission on the HumeLink project must include the Application number SSI-36656827



A submission must include your full name and address. You can request to have your name withheld



A submission must be signed



A submission must include a statement on whether you support, object, or are providing comments on the issues raised in the EIS



Submissions can be made by an individual or a group



A group submission signed by one person is considered a single submission

Where relevant, provide reasons and/ or supporting information for any conclusions made in the submission



If there is new information that should be considered, provide supporting documents



An effective submission considers the purpose of environmental impact assessment and refers to a relevant issue or key matter in the EIS

Submissions must be sent directly to the NSW Department of Planning and Environment (DPE). Transgrid cannot receive or send submissions to the DPE on behalf of submitters



Submissions must be received before midnight on the last day of the exhibition period



#### Lodging a submission




An online submission requires an account to be created on the NSW Major Projects Planning Portal



Online submissions must be made via the NSW Major Projects Planning Portal. Follow the step by step instructions on their website: <u>www.planning.nsw.gov.au/</u> <u>have-your-say</u>



### NSW DPE Major Projects Planning Portal




Development of new transmission lines between thw exisitng substations at Wagga Wagga and Bannaby and the proposed Maragle substation, and a new substation at Gugaa.

**Project Details** 



### **Digital EIS**



Transgrid operates and manages the high voltage electricity transmission network in NSW and the ACT, connecting generators, distributors, and major end users through 13,000 kilometres of existing high voltage transmission lines and 121 substations.

Transgrid's network forms the backbone of the National Electricity Market, enabling energy trading between Australia's three largest states along the east coast and supporting the competitive wholesale electricity market, while leading the transition to a clean energy future.


#### What is HumeLink?

Transgrid is proposing to increase the energy network capacity in southern NSW through the development of about 360 kilometres of new 500 kilovolt (kV) high-voltage transmission lines and associated infrastructure between Wagga Wagga, Bannaby and Maragle. The project is known as HumeLink. The project would be located across five Local Government Areas (LGAs).

When completed, HumeLink would achieve the objectives to:

- increase the transfer capacity between southern NSW and major load centres within NSW (Sydney, Newcastle and Wollongong)
- reinforce stability and reliability in the network
- facilitate transition of the network to connect new renewable generation.





WaggaWagga

M31

National Park

Overview


 $\equiv$ 

Existing Wagga 330 kV substation

Proposed Gugaa 500 kV substatio



## Questions



# Thank you

1800 31 73 67 (free call) humelink@transgrid.com.au **transgrid.com.au/humelink** 

HumeLink Community Engagement Team, PO BOX A1000, Sydney South, NSW 1235



Official

